



WINDOWS	
600X1200	0
900X1200	1
400X500 OBSCURE	0
BURGLAR BAR	YES
BLINDS	YES
DOORS	
SGL EXTERIOR	1
DBL EXTERIOR	0
INTERNAL	0
SECURITY GATE	1
CYLINDER LOCK	1
HATCH	0
BATHROOM	
TOILET	0
URINAL	0
BATH	0
SHOWER	0
BASIN H/C	0
GEYSER 200L	0
KITCHEN	
SINK UNIT 900	0
BASE UNIT 900	0
WALL UNIT 900	0
SHELVES	0
WORKTOP	0
WARDROBE	0
ELECTRICAL	
DB S/P	1
SGL FLUOR. LIGHT	1
DBL FLUOR. LIGHT	0
OUTSIDE LIGHTS	1
SGL LIGHT SWITCH	0
DBL LIGHT SWITCH	1
DAYLIGHT SWITCH	0
AC SPLIT 12000BTU	1
SOCKETS	
SINGLE 16 AMP	0
DOUBLE 16 AMP	1
A/C POINTS	1
GEYSER POINTS	0
STOVE POINTS	0
TEL. POINTS	0
OTHER	
STEEL CHASSIS	YES
VINYL FLOOR	YES
JACKS AND SLABS	4
STEPS	1
HAND RAIL	0



Team Engineers (Pty) Ltd  
Tel: (+267) 390 2520  
E-mail: info@team-botswana.com

CLIENT: **RENTAL**

DRAWING No.:  
**0303-OP RENTAL**

DESIGN: S.MMOLAI  
DATE: 21/01/2022  
CHECKED: SMMOLAI  
DATE: 28/02/2022

APPROVED:

DATE:

CHASSIS No.:

SCALE: 1:30

SIZE: A4

SHEET: 1 OF 3

PROJECT DESCRIPTION: FLOOR PLAN  
3 X 3M OPEN PLAN MOBILE UNIT.

REV NO: 00

REVISION COMMENTS:

NOTES:

1. UNLESS STATED OTHERWISE, ALL LINEAR MEASUREMENTS ARE IN MM AND ANGULAR MEASUREMENTS ARE IN DEGREES.
2. BOTH INTERNAL & EXTERNAL WALLS ARE MADE OF 60MM THICK CHROMADEK PANELS.