



WINDOWS	
600X1200	0
900X1200	2
400X500 OBSCURE	0
BURGLAR BAR	YES
BLINDS	YES
DOORS	
SGL EXTERIOR	2
DBL EXTERIOR	0
INTERNAL	0
SECURITY GATE	2
CYLINDER LOCK	2
BATHROOM	
TOILET	0
URINAL	0
SHOWER	0
BASIN	0
GEYSER 150L	0
KITCHEN	
SINK UNIT 900	0
BASE UNIT 900	0
WALL UNIT 900	0
WORKTOP	0
ELECTRICAL	
D.B (SINGLE PHASE)	1
SGL FLUOR. LIGHT	2
DBL FLUOR. LIGHT	0
OUTSIDE LIGHTS	2
SGL LIGHT SWITCH	0
DBL LIGHT SWITCH	2
DAYLIGHT SWITCH	0
AC SPLIT 9000BTU	0
AC SPLIT 12000BTU	2
SOCKETS	
SINGLE 16 AMP	0
DOUBLE 16 AMP	2
A/C POINTS	2
GEYSER POINTS	0
STOVE POINTS	0
OTHER	
STEEL CHASSIS	YES
VINYL FLOOR	YES
JACKS AND SLABS	6
STEPS	2



Team Engineers (Pty) Ltd
Tel: (+267) 390 2520
E-mail: info@team-botswana.com

CLIENT: RENTAL		CHASSIS No.:
DRAWING No.: 0603-2OFF RENTAL		
DESIGN: S.MMOLAI	APPROVED:	SCALE: 1:30
DATE: 14/01/2022		SIZE: A4
CHECKED: SMMOLAI	DATE:	SHEET:
DATE: 21/01/2022		00

PROJECT DESCRIPTION: FLOOR PLAN 6X3M TWO ROOMED OFFICE UNIT	
REV NO:	REVISION COMMENTS:
00	

NOTES:
1. UNLESS STATED OTHERWISE, ALL LINEAR MEASUREMENTS ARE IN MM AND ANGULAR MEASUREMENTS ARE IN DEGREES.
2. BOTH INTERNAL & EXTERNAL WALLS ARE MADE OF 60MM THICK CHROMADEK PANELS.